




Y ditch
Except 5HP Models



X-X cross section



Foundation bolt executing method



Model			A	B
RXYQ5MY1B RXY5MY1, YL, TL RX5MY1 RXYQ5MAY1, YL, TL RX(Y)Q5PY1	RXYQ5PYL, TL RXYQ5PAY1, Y6 RXYQ5PAYL, YLD RXQ5PAY1 RX5MAY1	RQYQ140PY1 RQYQ180PY1 RQEQ140PY1 RQEQ180PY1 RQEQ212PY1	497	697
RXYQ8 · 10MY1B REYQ8 · 10MY1B RXY8 · 10MY1, YL, TL RX8 · 10MY1 RXYQ8 · 10MAY1, YL, TL RHXY8 · 10MY1 RHXYQ8 · 10MAY1 RCXYQ8 · 10MAY1 RX(Y)Q8 · 10PY1 RZP250MAY1	RXM8MY1 RHXYQ8 · 10PY1 RCXYQ8 · 10PY1 RZP250 · 300PY1 RXYQ8 · 10PY1C RXYQ8 · 10PYL, TL RYCP250PY1 REMQ8 · 10 · 12PY1 RXM8MAY1 RQ200KY1	RXYQ8 · 10PAY1, Y6 RXYQ8 · 10PAYC RXYQ8 · 10PAYL, YLD RXQ8 · 10PAY1(S) RXYQ8PTLK RXYQ8PYNK RX8 · 10MAY1(S) RXM8MBY1(S) RXYN10AY1 RXYQ8 · 10PRY6	792	992
RXYQ12 · 14 · 16MY1B REYQ12 · 14 · 16MY1B RXY12 · 14 · 16MY1, YL, TL RX12 · 14 · 16MY1 RXYQ12 · 14 · 16MAY1, YL, TL RHXY12 · 14 · 16MY1 RHXYQ12 · 14 · 16MAY1 RCXYQ12 · 14 · 16MAY1 RXYQ8 · 10MY1K RXYQ8 · 10MYLK RX(Y)Q12 · 14 · 16 · 18PY1 RZP350MAY1	RXM10MY1 RHXYQ12 · 14 · 16PY1 RCXYQ12 · 14 · 16PY1 RXYQ12 · 14 · 16PY1C RXYQ12 · 14 · 16 · 18PYL, TL RZP350 · 400 · 450PY1 RYCP400PY1 REMQ14 · 16PY1 RXM10MAY1 RQ250KY1 RXYQ12 · 14 · 16 · 18PAY1, Y6 RXYQ12 · 14 · 16 · 18PAYL, YLD	RXYQ12 · 14 · 16PAYC RXQ12 · 14 · 16 · 18PAY1(S) RXYQ10 · 12PTLK RXYQ10 · 12PYNK RX12 · 14 · 16MAY1(S) RXM10MBY1(S) RXYQ12 · 14 · 16 · 18PRY6	1102	1302
REYQ8 · 10 · 12 · 14 · 16PY1(B) REYQ8 · 10 · 12 · 14 · 16P8Y1B			1162	1362

(Notes)

- The proportions of cement:sand:gravel for the concrete shall be 1:2:4, and the reinforcement bars that their diameter are 10mm, (approx. 300mm intervals) shall be placed.
- The surface shall be finished with mortar. The corner edges shall be chamfered.
- When the foundation is built on a concrete floor, rubble is not necessary. However, the surface of the section on which the foundation is built shall have rough finish.
- A drain ditch shall be made around the foundation to thoroughly drain water from the equipment installation area.
- When installing the equipment on a roof, the floor strength shall be checked, and water-proofing measures shall be taken.
- Y ditch is not necessary for 5HP Models.